No.	Particulars	Per	Contents	Rate	Rate to be quoted
				Rs. a. p.	
11	Tata's tested rolled steel girders including hoisting and fixing with drilling holes for fixing double girders at every 8' apart with ½" dia. bolts and nuts	Cwt.	130.07	14 0 0	
12	Boxing girders 12"×5" in section with brick in cement including wiring and cement plastering, etc., complete	F.ft.	210	0 6 0	
13	Boxing girders 13"×5" in section with brick in cement including wiring and cement plastering, etc., complete	"	277	0 8 0	
14	Providing and fixing Mysore Teakwood partition inside Rooms ⅓ panelled, ⅔ glazed, 1/16" thick ground glass panes with door arrangements and achme brass fittings, etc., complete	Sq.ft.	180	1 4 0	
15	Roofing with R.C.C. 1 : 2 : 4 with main reinforcement bars 5' c to c and diagonal bars 12" c to c 5" thick with 4" brick concrete and two courses of flat tiles and nice plastering bottom and top including 1½' R.C. projection	Sqr.	53.70	75 0 0	
16	R.C.C. chajja 4" thick 1 : 2 : 4 with main reinforcement bars 5" c to c and diagonal bars 12" c to c and plastering with composite mortar top bottom faces stepped cornice 3' projection, etc., 9" inside wall	Sq.ft.	1150	1 0 0	
17	Burnt stone parapet wall 1½' thick 1½' high with one line dressed over one course of dressed B. S. slab top 1"×2" stepped cutting and cement pointing	R.ft.	11½	1 12 0	
18	Do do 2' high	"	809	2 0 0	
19	Do do 3½' high	"	36	3 14 0	
20	Do do 5' high	"	18	6 0 0	
21	Providing and fixing C. I. down water pipe with bends bell mouths and clamps	"	240	2 0 0	
22	Providing and fixing wrought iron railing of approved design with teak frames	"	111	3 0 0	
23	Providing and fixing C. I. spiral stair from 1st floor to top of First floor	"	14	20 0 0	
24	Cement pointing to stone masonry with raking joints and cutting lines	Sqr.	103.19	3 0 0	
25	White washing two coats	"	47.35	0 4 0	
26	White silicate painting two coats	"	3.60	4 0 0	
27	Varnishing two coats (Jhenson and Nicklson) with one coat of wood filler	"	11.74	8 0 0	
28	Government Lac Factory Green painting three coats	"	4.00	5 0 0	
29	Carving letters 12" high as "TALUK OFFICES"	No.	12	1 0 0	
30	Providing and fixing galvanised pipe flag pole with guy wire, etc.	L. S.	..	..	

M. K. RAJAM IYENGAR,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 11th July 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 29th July 1939, for sinking a curb well of 20' dia. at Bandihalla, Ghati Subramanyam for improving Water Supply. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1939.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 284 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for sinking a curb well of 20' dia. at Bandihalla Ghati Subramanyam for improving Water Supply," in default of which tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Abstract estimate of quantities of work.

No.	Particulars	Unit	Quantity
1	Providing an Reinforced cement concrete curb ring 20 feet inner diameter $1\frac{3}{4}' \times 1\frac{1}{2}'$ with 1" R. S. bars for main reinforcement bent into the required curvature and fixed in position including brick mould for casting, etc., as per design	C.ft.	149
2	Earthwork excavation for sinking the curbing uniformly and lifting the earth and sand, etc., with water bye-pass—		
	(1) Do 1st fathom from G.L.	C.yd.	$96\frac{1}{2}$
	(2) Do 2nd fathom	,,	$96\frac{1}{2}$
	(3) Do 3rd fathom	,,	$48\frac{1}{4}$
3	Steining the well with burnt brick in cement mortar 1 : 6	C.ft.	1,825
4	Providing reinforced cement concrete band rings	,,	406
5	Cement plastering $\frac{1}{2}$" thick to the brick steining inside the well	Sqr.	12·57
6	Supplying and fixing R. S. girders 6" × 12" over the well for supporting R.C. slab roofing over the well	Cwt.	$34\frac{1}{2}$
7	Supplying and fixing reinforced cement concrete precast slab of 2" thick for covering the well	S.ft.	415
8	Providing and fixing C.I. manhole frame and covering over the roof 2' × 3'	Each	1
9	Providing iron ladder about 30' with 2" × $\frac{1}{2}$" flat iron uprights and $\frac{3}{4}$" dia. rods $2\frac{1}{2}'$ horizontals at one foot intervals including fixing, etc., complete	R.ft.	2

N. KRISHNIENGAR,
Sanitary Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE SUPERINTENDENT, GOVERNMENT PRINTING, BANGALORE.

Abstract Notification dated 18th July 1939.

The attention of the public is invited to the detailed notice, dated 7th July 1939, published on page 1345 of Part VI of the *Mysore Gazette*, dated 13th July 1939, regarding the sale by public auction of unserviceable articles at the Government Branch Press, Mysore, on Friday the 4th August 1939, at 3 P.M.

B. KRISHNASWAMY CHETTY,
Ag. *Superintendent.*